



ANNEX E2

EVENT AND ACTION PLAN FOR NOISE
MONITORING

ANNEX E2 EVENT AND ACTION PLAN FOR OPERATIONAL NOISE MONITORING

Action			
Event	ET	IEC	Contractor
Action Level	- Identify the source(s) and investigate the cause(s) of exceedance and complaint - Prepare Notification of Exceedance within 24 hours - Inform Contractor, IEC and Project Proponent whether the cause of exceedance is due to the Project - Discuss with Contractor and IEC for remedial measures required - Ensure remedial measures are properly implemented - Have additional monitoring if exceedance is due to the Project. If exceedance stops, cease additional monitoring	- Verify the Notification of Exceedance - Check monitoring data submitted by ET - Discuss with ET and Contractor on proposed remedial measures - Review proposals on remedial measures - Audit the implementation of the remedial measures - Audit the effectiveness of the implemented remedial measures	- Submit proposals for remedial measures to IEC - Implement the agreed proposals

Action			
Event	ET	IEC	Contractor
Limit Level	- Identify the source(s) and investigate the cause(s) of exceedance and complaint - Prepare Notification of Exceedance within 24 hours - Inform Contractor, IEC, Project Proponent and EPD whether the cause of exceedance is due to the Project - Analyse the operation of SENTX and investigate the causes of exceedance - Provide interim report to Contractor, IEC, Project Proponent and EPD the causes of the exceedances - Discuss with Contractor and IEC for remedial measures required - Ensure remedial measures are properly implemented - Report the remedial measures implemented and the additional monitoring results to Contractor, IEC, Project Proponent and EPD - Have additional monitoring if exceedance is due to the Project. If exceedance stops, cease additional monitoring	- Verify the Notification of Exceedance - Check monitoring data submitted by ET - Discuss with ET and Contractor on proposed remedial measures - Review proposals on remedial measures - Audit the implementation of the remedial measures - Audit the effectiveness of the implemented remedial measures	- Take immediate measures to avoid further exceedance - Submit proposals for remedial measures to IEC within 3 working days of notification - Implement the agreed proposals - Resubmit proposals if problem still not under control - Stop the relevant activity of works as determined by the Project Proponent until the exceedance is abated